



S70 SERIES STEEL SLIDING GUARD TOWER DETENTION WINDOWS SECTION 08651

PART 1 - GENERAL

1.1 DESCRIPTION

A. Work included:

1. Furnish all labor and materials to complete the fabrication of detention windows as shown on the architect's drawings and as specified herein. All detention windows covered by this specification shall be fabricated by Hope's Windows Inc., Jamestown, New York, whose name and products are used to establish the standard of workmanship and quality construction required for this project. Other bidders must be approved by the architect at least ten days prior to the bid date, through submission of samples and evidence showing that the bidder has been fabricating detention window products of this type and quality for at least five years. All windows must be domestically manufactured in the U.S.A. All work shall include, but not be limited to, the following.
2. Steel horizontal sliding type windows. Ventilators shall be hung on a bearing roller/rail system and operated by a recessed pull.
3. All window anchors, mullions, covers and trim.
4. Screens for operating ventilators (optional).
5. Factory applied Hope's finish.
6. Installation.

B. Related work specified elsewhere:

1. Glass, glazing and glazing materials, Section ____.
2. Perimeter caulking, Section ____.
3. Miscellaneous structural items, Section ____.
4. Anchors built in or encased in concrete, (embedments), Section ____.

1.2 QUALITY ASSURANCE

- ##### **A. Manufacturer shall have not less than (5) years experience in the fabrication of steel detention windows and be a member of The Steel Window Institute (SWI). Installation of windows shall be done by experienced window installers.**
- ##### **B. Allowable tolerances: Size dimensions + 1/16 inch.**
- ##### **C. Installation of windows shall be done by experienced window installers.**
- ##### **D. Source quality control:**
1. Air infiltration test:
 - a. Products must be independently lab tested in accordance with ASTM E283.
 - b. Air infiltration to meet or exceed 0.01 CFM/SQFT with differential pressure across window unit of 1.57 PSF.
 2. Water penetration test:
 - a. Products must be independently lab tested and meet or exceed ASTM E331.



S70 SERIES STEEL SLIDING GUARD TOWER DETENTION WINDOWS SECTION 08651

- b. No water penetration for 15 minutes when window is subjected to a rate of flow of 5 gal./hr/sq.ft with differential pressure across window unit of 2.86 PSF. Pressure determined per job specific design pressure.
- c. When weeps are required, ASTM E547 cyclic testing standard with differential pressure across window unit of 2.86 PSF shall be standard. Pressure determined per job specific design pressure.
- 3. Field testing criteria (when applicable) shall be in accordance with AAMA 502-12, procedure B
- 4. Upon request, the window manufacturer shall provide a test report from a qualified independent U.S. testing laboratory regularly engaged in testing windows to verify that products conform to test requirement as outlined.

1.3 SUBMITTALS

- A. Samples (as requested by architect)
- B. Shop drawings and manufacturer's literature:
 - 1. Submit for approval shop drawings showing window and installation details, including anchorage, fastening and recommended sealing methods within our systems.
 - 2. Dimensioned elevations showing window opening and window sizes.
 - 3. The manufacturer shall not commence any work until shop drawings have been returned "approved" with a stamp or signature.
 - 4. Color charts for finishes.

1.4 PRODUCT, STORAGE AND HANDLING

- A. The General Contractor shall be responsible for the protection and storage of the windows after delivery to the site.
- B. Store in designated areas in an upright position on wood slats or on a dry floor in a manner that will prevent damage. Ventilate canvas or plastic coverings to prevent humidity buildup.

1.5 WARRANTY

- A. Provide Hope's standard 1 year Limited Warranty.

PART 2 - PRODUCT AND FABRICATION

2.1 MANUFACTURERS

- A. Furnish all labor and materials to complete the fabrication of windows as shown on architect's drawings and as specified herein. All windows covered by this specification shall be domestically manufactured in the U.S.A.
- B. Manufacturers: Subject to compliance with requirements covered in this specification, provide products by Hope's Windows, Inc. – Jamestown, NY (phone: 716-665-5124, e-mail: sales@hopeswindows.com) whose name and products are used to establish the standard of workmanship.
- C. Substitutions: Written approval necessary 10 days prior to bid through submission of the following:
 - 1. Full-size window samples matching required scope.
 - 2. Applicable test reports as outlined in Quality Assurance Section 1.2
 - 3. List of (5) recently completed projects of similar size and scope.



S70 SERIES STEEL SLIDING GUARD TOWER DETENTION WINDOWS SECTION 08651

2.2 MATERIALS

- A. The perimeter framing and removable covers shall be formed from 12 gauge galvanized steel or 14 gauge stainless steel (depending on finish requirements).
- B. Ventilator jamb, head, and sill sections shall be 12 gauge formed steel, or 12 gauge formed stainless steel (depending on finish and glazing requirements).
- C. Bearing surfaces for the rollers shall be 10-gauge galvanized steel.
- D. Anchors shall be fabricated from structural angles with a minimum leg thickness of 3/16".
- E. Sill head, and jamb weather-stripped ventilator bedding stops shall be extruded aluminum alloy 6063-T5 with a minimum thickness of .125 inches.
- F. Glazing beads shall be formed from 12 gauge galvanized steel or 14 gauge stainless steel
- G. Roller/rail Hardware shall have sealed bearings and hardened steel races.
- H. Pulls used for operation shall be fabricated from red bronze.
- I. Security and detention screens (option select one):
 - 1. Fixed angle frame.
 - a. Frames shall be steel angles formed from 12 gauge steel or 14 gauge stainless steel.
 - b. Steel clamp strip shall be 12 gauge steel or 12 gauge stainless steel.
 - c. Screen cloth shall be stainless steel, Type 18/8, alloy #304, woven 12 mesh to the inch from 0.028" diameter wire, double crimped. (Option – stainless steel, Type 18/8, Alloy #304, woven 10 mesh to the inch from 0.047" diameter wire, double crimped).
 - 2. Operable steel detention screens (optional) are available.
 - a. Consult Hope's for details and specifications.
- J. Finishing:
 - 1. Pre-Treatment
 - 2. Primer- E-Coat (Electrodeposited epoxy primer).
 - 3. Finish coat – Ultrathane Polyurethane Top Coat.

2.3 FABRICATION

- A. Fabricate windows in accordance with approved shop drawings.
- B. Frame members shall be coped and welded at corners the full depth of the frame for maximum strength and weathertightness and exposed face welds dressed smooth.
- C. Jamb anchors shall be fabricated from steel angles with a minimum thickness of 7 gauge, located a maximum of 18" on center. (Optional) Jambs can be attached with anchor bolts located a maximum of 18" on center.
- D. Head and sill anchor bolts shall be located a maximum of 18" on center.



S70 SERIES STEEL SLIDING GUARD TOWER DETENTION WINDOWS SECTION 08651

- E. All removable covers or trim, either exterior or interior, shall be field attached with tamper-resistant screws, spaced not more than 9" on centers at the interior and spaced not more than 12" on centers at the exterior.
- F. Ventilator jamb, head, and sill bars shall be solidly welded and exposed faces and contact surfaces dressed smooth. The ventilator shall be mechanically fastened to the rail system.
- G. Operable Hardware:
 - 1. Rollers will be mechanically attached and located at the head and sill of the ventilator.
 - 2. Recessed pulls will be screw attached and located at the ventilator jamb
 - 3. Sliding window locks operate rated w/ a thumb turn located at the ventilator jamb.
 - 4. **Optional:** Slide bolt located at the ventilator sill
- H. The aluminum jamb, head and sill weather-stripped ventilator bedding stops shall be screw attached to the frame with screws spaced a maximum of 12" on center.
- I. Glazing:
 - 1. All ventilators shall be designed for inside glazing.
 - 2. Provide replaceable continuous glazing beads to suit the glass as specified.
 - 3. Glazing beads shall be cut and shop fitted to each glass lite prior to shipment.
 - 4. Glazing beads shall be attached with tamper-resisting screws spaced a maximum of 9" on center.
- J. Security and detention screens:
 - 1. Fixed angle frame.
 - a. Frames shall be welded solid at corners and welds dressed smooth.
 - b. Secure screen cloth to frame using special security screws spaced 4" on centers, which penetrate the frame, screen cloth and clamp strip.
 - c. The screen frame and clamp strip shall be factory finished to match the window finish.
 - d. Screen mesh shall be unfinished stainless steel
 - 2. Operable steel detention screens (**optional**):
 - a. Screen frames shall be finished to match the finish of the windows.
 - b. Consult Hope's for details and specifications.

2.4 FACTORY FINISHING

A. Cleaning

- 1. All hot-rolled steel profiles must be acid pickled as defined by SSPC – SP8 to ensure a pristine, white metal substrate prior to fabrication.

B. Pretreatment

- 1. Following welding and all machining operations, hot-rolled products and accessories are subjected to the following pretreatments geared specific to projects proximity to corrosive environment. Cold-rolled, formed sheet steel components are manufactured from A60 galvanized sheet and subjected to applicable processes outlined below.
- 2. 12-stage process



S70 SERIES STEEL SLIDING GUARD TOWER DETENTION WINDOWS SECTION 08651

- a. Alkaline cleaning spray
 - b. Alkaline cleaning – submersion
 - c. Water immersion rinse combo
 - d. Water immersion rinse clean
 - e. Acid immersion
 - f. Neutralizing rinse
 - g. Water immersion rinse clean
 - h. Conditioner immersion
 - i. Zinc phosphate immersion
 - j. Rinse immersion
 - k. Sealer immersion
 - l. Water reverse osmosis rinse immersion
3. Epoxy E-coat Primer:

All pickled and pretreated frames and accessories are immersed into an electrostatic (E-coat) bath of PPG epoxy primer to ensure all substrates are encapsulated evenly and completely. Use of spray primers only will not be an acceptable alternative to this process due to benefits from additional cleaning and frame submersion.

 - a. Permeate spray.
 - b. Permeate rinse.
 - c. Epoxy primer immersion and electrostatic encapsulation
 - d. Water reverse osmosis rinse
 - e. Oven-cure, 45 minutes @ 350° F
4. Acrylic Polyurethane Top Coat.
 - a. Following all pre-treatments, all products shall receive Hope's ultrathane polyurethane finish with touch-up capability, low chalking and fading characteristics. Select from Hope's Correctional Color Palette. Color matching is available upon request; some colors may require added cost. Consult your Hope's Representative for selection assistance.
5. Finish Overview:
 - a. Combined overall dry film thickness (DFT) shall be a minimum of 1.8 – 2.5 mils.
 - b. Overall process shall provide full documented compliance with the following criteria:
 - i. Acid Pickling: SSPC-SP8
 - ii. Paint Blistering: ASTM D714.
 - iii. Humidity: ASTM D4585.
 - iv. Painted Products in Corrosive Environment: ASTM D1654.



S70 SERIES STEEL SLIDING GUARD TOWER DETENTION WINDOWS SECTION 08651

- v. Salt Spray (Fog): ASTM B117.
- vi. Cyclic Fog/Dry (Prohesion): ASTM G85.
- vii. Salt Fog/UV Painted Metal: ASTM D5894.
- viii. Pull Off Strength of Coating: ASTM D4541.

C. 2B Finish (Stainless Steel)

- 1. Acid cleaning all welds to remove burn marks
- 2. Water reverse osmosis rinse

PART 3 – EXECUTION

3.1 INSPECTION

- A. Window openings shall conform with details, dimensions and tolerances shown on the window manufacturer's approved shop drawings.
- B. Conditions which may adversely affect the window installation must be corrected by the general contractor before installation commences.

3.2 INSTALLATION

- A. Windows specified under this section shall be installed by experienced personnel.
- B. Install windows in openings in strict accordance with approved shop drawings.
 - 1. Set windows plumb, level and true to line without warp or rack of frames or ventilators.
 - 2. At head and sill anchor windows securely to surrounding construction with anchor bolts suitable for the sounding conditions. At jambs use minimum 1" long welds at anchor points. Maximum distance between bolts and weld points will be 18".
 - 3. The exterior joints between the windows, trim and mullions shall be properly sealed watertight with an approved sealant and neatly pointed.
 - 4. All windows shall be completely checked and adjusted after installation and before glazing to assure proper fit of ventilator to frame and to assure the operating mechanism works freely and satisfactorily.
- C. Install security or detention screens (if specified).
- D. Repair any abraded areas of the factory finish.

3.3 CLEANING

- A. Window installer shall leave the window surfaces clean after installation and ready to receive glass and glazing. The window installer shall not be responsible for final cleaning.
- B. Any protection necessary due to cleaning adjacent materials shall be the responsibility of the general contractor.